

Existing trees, street light poles, hydrants and other utility poles are to remain in place during construction unless otherwise noted in the plan. Conduct an on-site visit prior to bidding to determine any special measures required for proper clearance between the trees, hydrants and poles and the paving equipment. No additional compensation will be made.

## **K All Work Restrictions**

Excavation material and cleared and grubbed material should be stockpiled on upland areas an adequate distance away from wetlands, storm sewer inlets, floodplains, and the waterways as determined by engineer.

Provide the Wisconsin State Patrol, Milwaukee County Highway Maintenance, the City of Milwaukee Police Department, the City of Wauwatosa Police Department, the Village of Elm Grove Police Department, the City of Brookfield Police Department, and Milwaukee County Sheriff's Department with a 24-hour emergency contact number for when maintenance is required.

### **Replace standard spec 108.10.2.2(2) with the following:**

Include requests for severe weather delays in the Monthly CPM Progress Schedule Updates. Indicate the number of adverse weather days that occurred during that month. Provide CPM progress schedule documentation as required under Section 108.4.7 of the Baseline CPM Progress Schedule/Monthly CPM Progress Schedule Updates special provision to show that the controlling item of work was delayed. Show that the delay was beyond the control of the contractor. The engineer will assess the contractor's submittal and indicate how many adverse weather days are confirmed.

### **Replace standard spec 108.10.2.2(3) with the following:**

For each calendar month, the engineer will grant a severe weather day for each confirmed adverse weather day that exceeds the number of anticipated adverse weather days 108.10.2.2(1) shows. When the contractor requests severe weather days, the engineer will give the contractor a monthly written statement showing the number of days credited for severe weather. The engineer will only extend time for interim and contract completion dates for severe weather days that have been validated through an accepted CPM Progress Schedule Update.

## **L Interim and Final Completion of Work**

### **L.1 Interim Completion of Work 113th Street closure for sanitary sewer**

*Supplement standard spec 108.11 as follows:*

If the contractor fails to complete all backfilling, grading, and roadway restoration, as shown in Stage 1A to restore traffic on 113<sup>th</sup> Street south of Meinecke within 42 calendar days of the closure date, the department will assess the contractor \$500.00 in interim liquidated damages for each calendar day that 113<sup>th</sup> Street remains closed after 12:01 AM, on the 43<sup>rd</sup> calendar day after the closure begins. An entire calendar day will be charged for any period of time within a calendar day that 113<sup>th</sup> Street south of Meinecke is not open to at least one lane beyond 12:01 AM, on the 43<sup>rd</sup> day.

### **L.2 Interim Completion of Work SB IH 41/USH 45 Lane Reduction to construct Temporary Shoofly Structure Pier and barrier transition**

*Supplement standard spec 108.11 as follows:*

If the contractor fails to complete all south pier construction, barrier transition construction, backfilling, and roadway restoration, as shown in Stage 1C Substage 1 to restore IH 41/USH 45 to three lanes southbound within 28 calendar days of the closure date, the department will assess the contractor \$50,000.00 in interim liquidated damages for each calendar day that SB IH 41/USH 45 is not open to three lanes after 12:01 AM, on the 29<sup>th</sup> calendar day after the closure begins. An entire calendar day will be charged for any period of time within a calendar day that SB IH 41/USH 45 is not open to at least three lanes beyond 12:01 AM, on the 29<sup>th</sup> day.